

AD-A121 661

COMPUTERIZED CIVIL WORKS CONSTRUCTION COST INDEX  
SYSTEM: USER'S MANUAL(U) CONSTRUCTION ENGINEERING  
RESEARCH LAB (ARMY) CHAMPAIGN IL D G BAGBY ET AL.  
OCT 82 CERL-TR-P-135

1/

UNCLASSIFIED

F/G 13/2


NL

END

DATE

FILED

DTIC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

construction  
engineering  
research  
laboratory



United States Army  
Corps of Engineers  
... Serving the Army  
... Serving the Nation

TECHNICAL REPORT P-135  
October 1982

COMPUTERIZED CIVIL WORKS CONSTRUCTION  
COST INDEX SYSTEM: USERS' MANUAL

AD A121661

by  
D. Gordon Bagby  
Shahid Siddiqi

DTIC  
ELECTE  
NOV 22 1982  
A



82 11 22 101

Approved for public release; distribution unlimited.

The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official indorsement or approval of the use of such commercial products. The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

**DESTROY THIS REPORT WHEN IT IS NO LONGER NEEDED  
DO NOT RETURN IT TO THE ORIGINATOR**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS REPORT COMPLETION FORM
1. REPORT NUMBER CERL-TR-P-135	2. GOVT ACCESSION NO. AD A121 661	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) COMPUTERIZED CIVIL WORKS CONSTRUCTION COST INDEX SYSTEM: USERS' MANUAL	5. TYPE OF REPORT & PERIOD COVERED FINAL	
	6. PERFORMING ORG. REPORT NUMBER	
7. AUTHOR(s) D. Gordon Bagby Shahid Siddiqi	8. CONTRACT OR GRANT NUMBER(s) IAO CWE-BA-81-11	
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. ARMY CONSTRUCTION ENGINEERING RESEARCH LABORATORY P.O. BOX 4005, CHAMPAIGN, IL 61820	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
11. CONTROLLING OFFICE NAME AND ADDRESS	12. REPORT DATE October 1982	
	13. NUMBER OF PAGES 29	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)	15. SECURITY CLASS. (of this report) UNCLASSIFIED	
	15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES  Copies are obtainable from the National Technical Information Service Springfield, VA 22151		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)  Civil Works Construction Cost Index System estimates construction		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) ↓ Costs for U.S. Army Corps of Engineers civil works projects are first estimated before concept designs are prepared. These projects are not immediately authorized for construction; in fact, it may be several years before appropriations are made for even the detailed design phase. During this time, inflation usually makes the current costs higher than previously estimated.  For programming requirements, the estimates must be updated annually. Corps districts can do this in two ways: (1) performing a detailed re-		

DD FORM 1 JAN 78 1473 EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

**UNCLASSIFIED**

**SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)**

**BLOCK 20. CONT'D.**

estimate, or (2) applying an inflation factor to the latest estimate. Both methods have advantages and disadvantages. Re-estimating gives results that are at least as accurate as the prior estimate, but it is very time-consuming and is therefore not practical to do annually because of the limited number of personnel available at the district level. Updating using an inflation factor can be done very quickly, with acceptable accuracy.

The U.S. Army Construction Engineering Research Laboratory (CERL) has developed a system of indices — the Civil Works Construction Cost Index System (CWCCIS) — specifically for updating civil works construction costs before the official Government estimate for contract award. The Office of the Chief of Engineers asked CERL to computerize this system so that the calculations needed to change index values and update estimates could be done automatically. This report provides instructions for users of the computerized CWCCIS.

**UNCLASSIFIED**

**SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)**

# FOREWORD

This study was done for the Directorate of Civil Works, Office of the Chief of Engineers (OCE), under IAO CWE-BA-81-11. The OCE Technical Monitor was E. B. Wilsie, DAEN-CWE-BA.

The Facilities Systems Division (FS), U.S. Army Construction Engineering Research Laboratory (CERL), did this study. Mr. E. A. Lotz is Chief of CERL-FS.

COL Louis J. Circeo is Commander and Director of CERL, and Dr. L. R. Shaffer is Technical Director.

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
Distribution/	
Availability Codes	
Avail and/or	
Special	
A	

## CONTENTS

	<u>Page</u>
DD FORM 1473	1
FOREWORD	3
LIST OF TABLES AND FIGURES	5
1 INTRODUCTION.....	7
Background	
Objective	
Approach	
Mode of Technology Transfer	
2 USING THE COMPUTERIZED CWCCIS.....	9
System Overview	
Accessing Computerized CWCCIS	
Getting Help	
Using the System	
Logging Out	
APPENDIX: CWCCIS and the Principles of Cost Indexing	22
DISTRIBUTION	



## TABLES

<u>Number</u>		<u>Page</u>
1	Cross-Reference for Programs and Files	9
A1	Features for Which Indices Were Developed	23
A2	Costs of Four Construction Inputs	26
A3	Costs of Five Construction Inputs	26
A4	Costs of Four Construction Inputs -- Price of Labor in Minutes	29
A5	Quantity Weighting Scheme	29
A6	Items Surveyed to Derive Quantity Weights	29

## FIGURES

1	Output for COSTIND Option 1	13
2	Output for COSTIND Option 2	15
3	Output for COSTIND Option 3	17
4	Output for COSTIND Option 4	19
A1	Hierarchy of Levels in CWCCIS	24

COMPUTERIZED CIVIL WORKS  
CONSTRUCTION COST INDEX  
SYSTEM: USERS' MANUAL

## 1 INTRODUCTION

### Background

The costs for U.S. Army Corps of Engineers civil works projects are first estimated before concept designs are prepared. These projects are not immediately authorized for construction; in fact, it may be several years before appropriations are made for even the detailed design phase. During this time, inflation usually makes the current costs higher than previously estimated.

For programming requirements, the estimates must be updated annually. Corps districts can do this in two ways: (1) performing a detailed re-estimate, or (2) applying an inflation factor to the latest estimate. Both methods have advantages and disadvantages. Re-estimating gives results that are at least as accurate as the prior estimate, but it is very time-consuming and is therefore not practical to do annually because of the limited number of personnel available at the district level. Updating using an inflation factor can be done very quickly, with acceptable accuracy.

The U.S. Army Construction Engineering Research Laboratory (CERL) has developed a system of indices -- the Civil Works Construction Cost Index System (CWCCIS) -- specifically for updating civil works construction costs before the official Government estimate for contract award.<sup>1</sup> (The appendix explains the principles of cost indexing.) The Office of the Chief of Engineers asked CERL to computerize this system so that the calculations needed to change index values and revise estimates could be done automatically.

### Objective

The objective of this report is to provide instructions for users of the computerized CWCCIS.

### Approach

CERL's experiences with CWCCIS and with field testing of the computerized system were used to develop the procedures described in this report.

<sup>1</sup> U. R. Poskus, Civil Works Construction Cost Index System (CWCCIS), Technical Report P-85/ADA048102 (U.S. Army Construction Engineering Research Laboratory [CERL], 1977).

Mode of Technology Transfer

It is recommended that the information in this report be incorporated in Engineer Manual (EM) 1110-2-1301, Engineering and Design: Cost Estimates — Planning and Design Stages.

## 2. USING THE COMPUTERIZED CWCCIS

This chapter explains how to access and use the CWCCIS interactive system, which resides on Boeing Computer Service's (BCS's) EKS-1 subsystem, a bank of Cyber 175 computers. To keep the computerized CWCCIS current, the Office of the Chief of Engineers updates the cost information used by the system.

### System Overview

The computerized CWCCIS is used on interactive, remote terminals available at all Corps districts and divisions. To access CWCCIS, the user signs on with his/her account and password; the program then gives instructions about operating the system. (Experienced users may bypass the explanation and proceed immediately to requesting information.) The user provides information about the type of cost index report and time period he/she wants. The computer lists the costs for the project, breaking them down by component (e.g., labor, cement, steel). If the user wants to determine the probable costs of a project planned for the future, he/she can request a cost projection for the future date.

Table 1 is a cross-referenced list of the files and programs or procedures CWCCIS requires when a user wants to compute cost indices. The first

Table 1

#### Cross-Reference for Programs and Files

<u>Program/File Name</u>	<u>Function</u>	<u>Programs Which Use This File</u>
COSTIND	Procedure user calls to compute project cost indices.	COSTIND
CWCI	FORTTRAN source used by COSTIND.	CWCI COSTIND
BCWCI	Binary compilation of CWCI for actual execution by COSTIND.	BCWCI COSTIND
WEIGHT	Data file containing the weighted proportions of earth, concrete, etc., required for each project. The format used is: 14X,5F7.4.	WEIGHT COSTIND CWCI BCWCI
HELPCI	A procedure which lists the user introductory help text in file HELPCIT.	HELPCI HELPCIT
HELPCIT	A text file containing a user help facility. This explains how to use the CWCI program and how to input information.	HELPCIT HELPCI

column gives the name of the program or procedure and the permanent file in which it resides. The second column lists the function of the program or describes the data in the file. The third column lists all programs which use the file. The list begins with this file's name, followed by the programs or files it requires.

#### Accessing Computerized CWCCIS

The user can access computerized CWCCIS by dialing the local or toll-free telephone number supplied with a BCS account. After dialing this number and obtaining the carrier, the user presses the CARRIAGE RETURN (CR) key a few times. The computer responds:

welcome to the bcs network  
your access port is ciy 039

select desired service:

The user types "eksl". The computer responds:

82/05/12. 10.37.50.  
EKS1 760K.N0501.54 B 82/05/02.DS-0 03.07.52. 82/05/12.

SIGNON:

The user enters his/her BCS account sign-on -- usually a six-character alphanumeric code. When CR is pressed, the computer responds with:

PASSWORD:

The user then enters the password associated with the sign-on for his/her account. When the CR key is pressed again, the computer flashes the time (Pacific standard time) and the user's terminal number.\* After the terminal number is printed, the computer asks the user to enter a one- to six-character name for identification; the user finishes accessing by typing his/her name and pressing CR.

#### Getting Help

By typing in "call,helpci/un=cecalb" or "-helpci/un=cecalb", the new user can print out an introduction to the Cyber 175 and instructions for computerized CWCCIS. The HELPCI document describes the use of several keys on the terminal:

1. RETURN or CR: This key is used to tell the computer to accept what has been typed in since the last RETURN or CR.

---

\* This number is important because it must be used to continue working if there is a telephone line failure or interruption. For a complete description of the procedure, refer to the Mainstream -- EKS Interactive Time Sharing (KIT) Users Manual, published by BCS.

2. CNTRL S: The output is interrupted when these keys are pressed simultaneously. This may be thought of as a pause function.

3. CNTRL Q: When these keys are pressed, the printing of output begins exactly where it stopped when CNTRL S was activated.

4. CNTRL H: When these keys are pressed simultaneously, the computer backspaces, allowing the user to type over errors and continue with the correct input. This is done with the BACKSPACE key on some terminals.

5. ESC or DEL: When one of these keys is pressed, the computer rejects the line just typed. In other words, every character typed in since the last RETURN or CR is rejected. When ESC or DEL is pressed, the computer responds with \*DEL\*; the user then revises.

### Using the System

After the HELPCI document has been printed, the computer responds with READY, which means that it will accept commands. The user then types in "call,costind/un=cecelb" or "-costind/un=cecelb". This calls up the interactive COSTIND procedure, which prompts the user for all input needed in the index calculations.

Note: The user is first asked to enter the code for the type of terminal he/she is using (e.g., see Figure 1). If this terminal is not listed, the ALP code can be used for any device.

COSTIND allows the user the following options in calculating cost indices:

1. The cost index of just one construction feature (Table A1) for a given quarter and year.
2. The cost indices for a given quarter and year for all 19 construction features.
3. The cost index for a given quarter and year for one particular feature, and a projection of that index for a future quarter and year. (The output includes a graph of the cost trend; this is available both on graphics and alphanumeric terminals.)
4. The cost indices for all 19 features and a projection of these indices for a future quarter and year.

For options 2 and 4, pie charts displaying the relative size of each index are available if the user types "pie" when prompted by the program. Users on nongraphic terminals should avoid these options because they take too much time on such equipment. For option 4, two pie charts are displayed — one for the present quarter and one for the future quarter and year for which indices are projected. With option 2, only the pie chart for the present quarter is displayed.

Option 3 projects the cost index for future years by using a linear least squares fit. The index is extrapolated along a straight line plotted through the past 12 quarters of index data.

Figures 1 through 4 are examples of the outputs corresponding to the four options above. All the user input is shown in lower-case letters; the output produced by the computer is in upper-case letters. The user input always appears after the symbol I>, which the computer prints to prompt the user.

If there are problems during the program, type in "stop"; this will terminate any instruction the computer is executing. The machine will respond \*TERMINATED\*, and the user can start again.

#### Logging Out

When the user is finished, he/she types "bye" and presses the CR key. The computer then logs out the user and responds with the charges for the session. If the user logs out by mistake, he/she can sign on and start again.

IDLE.  
C>-costind/un=cecelb  
12.35.31. WHEN ASKED FOR "DEVICE-" PRESS RETURN KEY TO GET A LIST  
12.35.31. OF DEVICES TYPES AVAILABLE. THEN TYPE IN APPROPRIATE TYPE  
12.35.31. OF DEVICE EXACTLY AS WRITTEN IN THE LIST OF DEVICES.  
12.35.31. FOR HELP CALL SIDDIQI, U OF ILL. 217-333-3146.  
DEVICE-  
I>  
LEGAL DEVICE CODES ARE:  
ALP - ALPHANUMERIC TERMINALS (80 COLS)  
C93 - CALCOMP 935 PLOTTER  
PTR - LINE PRINTER (120 COLS)  
RJE - REMOTE PLOTTING  
TEK - TEKTRONIX 4010/4013 TERMINALS  
TK4 - TEKTRONIX 4014/4015 TERMINALS  
T27 - TEKTRONIX 4027 TERMINAL  
T62 - TEKTRONIX 4014/4015 TERMINALS & TEKTRONIX 4662  
T63 - TEKTRONIX 4014/4015 TERMINALS & TEKTRONIX 4663  
T41 - TEKTRONIX 4114 TERMINAL  
DR4 - TEKTRONIX 4014/4015 TERMINALS & CALCOMP PLOTTER  
DEVICE-  
I>alp  
WELCOME TO THE CERL CIVIL WORKS COST COMPUTING INDEX  
PROGRAM DESIGNED BY SIDDIQI & STAMAS OF CERL CHAMPAIGN, ILL  
TYPE IN THE DESIRED INPUT AFTER THE COMPUTER TYPES:  
I>  
IF YOU MAKE A MISTAKE PRESS THE CONTROL KEY & H SIMULTANEOUSLY  
THIS WILL BACK SPACE YOU & ALLOW YOU TO OVERWRITE CHARACTERS  
IF YOU WISH TO STOP ANYWHERE TYPE IN -- STOP  
TYPE IN THE QUARTER & YEAR DESIRED FOR INDEX CALCULATION  
ENTER THESE AS - 1 1976 - TO INDICATE THE 1ST QUARTER OF 1976  
(DONT TYPE IN THE -), VALID YEAR CHOICES ARE 1975-1981  
THE INDEX IS BASED ON 1967=100  
I>1 1981  
TYPE IN USER LEVEL, TYPE IN -E- FOR EXPERT USER  
THIS ALLOWS YOU TO TYPE ALL INPUTS WITHOUT DETAILED WORDING  
IF NOVICE USER TYPE ANY CHARACTER OTHER THAN E  
I>tyro  
TYPE IN THE TYPE OF PROGRAM OUTPUT DESIRED  
TYPE IN - FULL - IF RESULTS AS WELL AS INPUT WEIGHTS DESIRED  
TYPE IN WORD - PART - IF ONLY THE RESULTS DESIRED  
I>part

Figure 1. Output for COSTIND option 1.



CHOOSE ONE OF THE FOLLOWING PROJECTS FOR CALCULATION  
 CHOICE DESIRED MUST BE A PROJECT NO. FROM 1-19 (ON LEFT)  
 EG. 5 IS POWER PLANTS. IF ALL PROJECTS COST INDICES DESIRED  
 TYPE IN ANY + NUMBER OTHER THAN 1-19

1 03 RESERVOIR •  
 2 04A EARTH DAM •  
 3 04B CONCRETE DAM •  
 4 05 LOCK •  
 5 07 POWER PLANTS •  
 6 08A ROADS •  
 7 08B1 CONCRETE BRIDGE•  
 8 08B2 STEEL BRIDGE •  
 9 08C RAIL ROAD •  
 10 09A CHANNELS & CANALS•  
 11 09B CHANNELS & CANALS•  
 12 10 BREAK WATERS •  
 13 11A LEVEES •  
 14 11B LEVEES •  
 15 11C LEVEES •  
 16 13 PUMPING PLANTS •  
 17 15 FLOODWAY CONTROL•  
 18 16A BANK STABILIZATION•  
 19 16B BANK STABILIZATION•

I>1

TYPE IN THE QUARTER & YEAR FOR WHICH YOU WISH TO  
 PROJECT THE COST INDICES. TYPE THEM IN THE SAME WAY AS BEFORE  
 EG. 1 1985. DO NOT SPECIFY A YEAR BEYOND 1985  
 IF NO PROJECTION DESIRED TYPE IN-- 0 0

I>0 0

CONSTRUCTION COST INDICES FOR QUARTER 1 OF YEAR 1981

CONSTRUCTION COST INDEX FOR 03 RESERVOIR •

	LABOR	PLANT	MATERIAL	INDEX
EARTH	296.097	312.739	283.777	300.009
CONCRETE	0.000	0.000	0.000	0.000
STEEL	0.000	0.000	0.000	0.000
MECHANICA	0.000	0.000	0.000	0.000
ELECTRICA	0.000	0.000	0.000	0.000

1 03 RESERVOIR 300.009

PAUSE TO CONTINUE TYPE- GO, TO STOP TYPE- STOP  
 I>go  
 \*  
 C>

Figure 1. (Cont'd).

```

IDLE.
C>-costind/un = CRcelb
12.41.11. WHEN ASKED FOR "DEVICE-" PRESS RETURN KEY TO GET A LIST
12.41.11. OF DEVICES TYPES AVAILABLE. THEN TYPE IN APPROPRIATE TYPE
12.41.11. OF DEVICE EXACTLY AS WRITTEN IN THE LIST OF DEVICES.
12.41.11. FOR HELP CALL SIDDIQI, U OF ILL. 217-333-3146.
DEVICE-
I>alp

WELCOME TO THE CERL CIVIL WORKS COST COMPUTING INDEX
PROGRAM DESIGNED BY SIDDIQI & STAMAS OF CERL CHAMPAIGN, ILL
TYPE IN THE DESIRED INPUT AFTER THE COMPUTER TYPES:

I>

IF YOU MAKE A MISTAKE PRESS THE CONTROL KEY & H SIMULTANEOUSLY
THIS WILL BACK SPACE YOU & ALLOW YOU TO OVERWRITE CHARACTERS
IF YOU WISH TO STOP ANYWHERE TYPE IN -- STOP

TYPE IN THE QUARTER & YEAR DESIRED FOR INDEX CALCULATION
ENTER THESE AS - 1 1976 - TO INDICATE THE 1ST QUARTER OF 1976
(DONT TYPE IN THE -), VALID YEAR CHOICES ARE 1975-1981
THE INDEX IS BASED ON 1967=100
I>1 1981

TYPE IN USER LEVEL, TYPE IN ~E~ FOR EXPERT USER
THIS ALLOWS YOU TO TYPE ALL INPUTS WITHOUT DETAILED WORDING
IF NOVICE USER TYPE ANY CHARACTER OTHER THAN E
I>novice

TYPE IN THE TYPE OF PROGRAM OUTPUT DESIRED
TYPE IN - FULL - IF RESULTS AS WELL AS INPUT WEIGHTS DESIRED
TYPE IN WORD - PART - IF ONLY THE RESULTS DESIRED
I>part.,

CHOOSE ONE OF THE FOLLOWING PROJECTS FOR CALCULATION
CHOICE DESIRED MUST BE A PROJECT NO. FROM 1-19 (ON LEFT)
EG. 5 IS POWER PLANTS. IF ALL PROJECTS COST INDICES DESIRED
TYPE IN ANY + NUMBER OTHER THAN 1-19
1      03  RESERVOIR      •
2      04A EARTH DAM      •
3      04B CONCRETE DAM   •
4      05  LOCK           •
5      07  POWER PLANTS   •
6      08A ROADS          •
7      08B1 CONCRETE BRIDGE•
8      08B2 STEEL BRIDGE  •
9      08C RAIL ROAD      •
10     09A CHANNELS & CANALS•
11     09B CHANNELS & CANALS•
12     10  BREAK WATERS   •
13     11A LEVEES         •
14     11B LEVEES         •
15     11C LEVEES         •
16     13  PUMPING PLANTS •
17     15  FLOODWAY CONTROL•
18     16A BANK STABILIZATION•
19     16B BANK STABILIZATION•
I>20

```

Figure 2. Output for COSTIND option 2.

AS INDICES FOR ALL 19 PROJECTS ARE DESIRED YOU HAVE THE  
 OPTION OF SKIPPING THE INTERMEDIATE DISPLAY OF THE COMPONENTS OF  
 EACH INDEX. IF YOU WISH TO TAKE THIS SKIP, TYPE IN - - SKIP - -  
 OTHERWISE TYPE IN ANY OTHER CHARACTER  
 I>skip

TYPE IN THE QUARTER & YEAR FOR WHICH YOU WISH TO  
 PROJECT THE COST INDICES. TYPE THEM IN THE SAME WAY AS BEFORE  
 EG. 1 1985. DO NOT SPECIFY A YEAR BEYOND 1985  
 IF NO PROJECTION DESIRED TYPE IN-- 0 0

I>0 0

# CONSTRUCTION COST INDICES FOR QUARTER 1 OF YEAR 1981

## THE PROJECT INDICES FOR QUARTER 1 OF YEAR 1981

1	03	RESERVOIR	300.009
2	04A	EARTH DAM	291.602
3	04B	CONCRETE DAM	290.936
4	05	LOCK	290.510
5	07	POWER PLANTS	282.490
6	08A	ROADS	293.310
7	08B1	CONCRETE BRIDGE	290.750
8	08B2	STEEL BRIDGE	296.299
9	08C	RAIL ROAD	300.037
10	09A	CHANNELS & CANA	288.692
11	09B	CHANNELS & CANA	298.518
12	10	BREAK WATERS	297.866
13	11A	LEVEES	287.678
14	11B	LEVEES	303.331
15	11C	LEVEES	297.479
16	13	PUMPING PLANTS	291.550
17	15	FLOODWAY CONTRO	293.792
18	16A	BANK STABILIZAT	276.894
19	16B	BANK STABILIZAT	281.404

PAUSE TO CONTINUE TYPE- GO, TO STOP TYPE- STOP

I>go

C>

Figure 2. (Cont'd).

IDLE.

C>-costind/un=cecelb

12.51.10. WHEN ASKED FOR "DEVICE-" PRESS RETURN KEY TO GET A LIST  
12.51.10. OF DEVICES TYPES AVAILABLE. THEN TYPE IN APPROPRIATE TYPE  
12.51.10. OF DEVICE EXACTLY AS WRITTEN IN THE LIST OF DEVICES.  
12.51.10. FOR HELP CALL SIDDIQI, U OF ILL. 217-333-3146.

DEVICE-

I>alp

WELCOME TO THE CERL CIVIL WORKS COST COMPUTING INDEX  
PROGRAM DESIGNED BY SIDDIQI & STAMAS OF CERL CHAMPAIGN, ILL  
TYPE IN THE DESIRED INPUT AFTER THE COMPUTER TYPES:

I>

IF YOU MAKE A MISTAKE PRESS THE CONTROL KEY & H SIMULTANEOUSLY  
THIS WILL BACK SPACE YOU & ALLOW YOU TO OVERWRITE CHARACTERS  
IF YOU WISH TO STOP ANYWHERE TYPE IN -- STOP

TYPE IN THE QUARTER & YEAR DESIRED FOR INDEX CALCULATION  
ENTER THESE AS - 1 1976 - TO INDICATE THE 1ST QUARTER OF 1976  
(DONT TYPE IN THE -), VALID YEAR CHOICES ARE 1975-1981  
THE INDEX IS BASED ON 1967=100

I>1 1981

TYPE IN USER LEVEL, TYPE IN -E- FOR EXPERT USER  
THIS ALLOWS YOU TO TYPE ALL INPUTS WITHOUT DETAILED WORDING  
IF NOVICE USER TYPE ANY CHARACTER OTHER THAN E  
I>e

TYPE IN, ON 1 LINE, PROJ NO., PROJECTED QUARTER,  
PROJECTED YEAR, & ON NEXT LINE, SKIP IF SKIP OPTION DESIRED

I>22            0        0

I>skip

Figure 3. Output for COSTIND option 3.

# CONSTRUCTION COST INDICES FOR QUARTER 1 OF YEAR 1981

## THE PROJECT INDICES FOR QUARTER 1 OF YEAR 1981

1	03	RESERVOIR	300.009
2	04A	EARTH DAM	291.602
3	04B	CONCRETE DAM	290.936
4	05	LOCK	290.510
5	07	POWER PLANTS	282.490
6	08A	ROADS	293.310
7	08B1	CONCRETE BRIDGE	290.750
8	08B2	STEEL BRIDGE	296.299
9	08C	RAIL ROAD	300.037
10	09A	CHANNELS & CANA	288.692
11	09B	CHANNELS & CANA	298.518
12	10	BREAK WATERS	297.866
13	11A	LEVEES	287.678
14	11B	LEVEES	303.331
15	11C	LEVEES	297.479
16	13	PUMPING PLANTS	291.550
17	15	FLOODWAY CONTRO	293.792
18	16A	BANK STABILIZAT	276.894
19	16B	BANK STABILIZAT	281.404

PAUSE TO CONTINUE TYPE- GO, TO STOP TYPE- STOP  
I>go  
\*  
C>

Figure 3. (Cont'd).

IDLE.

C>-costind/un=cecelb

12.27.20. WHEN ASKED FOR "DEVICE-" PRESS RETURN KEY TO GET A LIST  
12.27.20. OF DEVICES TYPES AVAILABLE. THEN TYPE IN APPROPRIATE TYPE  
12.27.20. OF DEVICE EXACTLY AS WRITTEN IN THE LIST OF DEVICES.  
12.27.20. FOR HELP CALL SIDDIQI, U OF ILL. 217-333-3146.

DEVICE-

I>alp

WELCOME TO THE CERL CIVIL WORKS COST COMPUTING INDEX  
PROGRAM DESIGNED BY SIDDIQI & STAMAS OF CERL CHAMPAIGN, ILL  
TYPE IN THE DESIRED INPUT AFTER THE COMPUTER TYPES:

I>

IF YOU MAKE A MISTAKE PRESS THE CONTROL KEY & H SIMULTANEOUSLY  
THIS WILL BACK SPACE YOU & ALLOW YOU TO OVERWRITE CHARACTERS  
IF YOU WISH TO STOP ANYWHERE TYPE IN -- STOP

TYPE IN THE QUARTER & YEAR DESIRED FOR INDEX CALCULATION  
ENTER THESE AS - 1 1976 - TO INDICATE THE 1ST QUARTER OF 1976  
(DONT TYPE IN THE -), VALID YEAR CHOICES ARE 1975-1981  
THE INDEX IS BASED ON 1967=100  
I>4 1981

TYPE IN USER LEVEL, TYPE IN -E- FOR EXPERT USER  
THIS ALLOWS YOU TO TYPE ALL INPUTS WITHOUT DETAILED WORDING  
IF NOVICE USER TYPE ANY CHARACTER OTHER THAN E  
I>e

TYPE IN, ON 1 LINE, PROJ NO., PROJECTED QUARTER,  
PROJECTED YEAR, & ON NEXT LINE, SKIP IF SKIP OPTION DESIRED

I>22 4 1984  
I>skip

Figure 4. Output for COSTIND option 4.

TYPE -PIE- IF PIE CHART COMPARISION OF 19 PROJECT  
INDICES DESIRED (TIME CONSUMING ON NON GRAPHICS TERMINALS)  
OTHERWISE TYPE IN ANY OTHER CHARACTER.

I>nopie

# CONSTRUCTION COST INDICES FOR QUARTER 4 OF YEAR 1981

## THE PROJECT INDICES FOR QUARTER 4 OF YEAR 1981

1	03	RESERVOIR	330.694
2	04A	EARTH DAM	314.247
3	04B	CONCRETE DAM	309.639
4	05	LOCK	311.655
5	07	POWER PLANTS	305.466
6	08A	ROADS	317.333
7	08B1	CONCRETE BRIDGE	310.092
8	08B2	STEEL BRIDGE	317.614
9	08C	RAIL ROAD	317.466
10	09A	CHANNELS & CANA	311.558
11	09B	CHANNELS & CANA	324.230
12	10	BREAK WATERS	322.026
13	11A	LEVEES	311.476
14	11B	LEVEES	327.776
15	11C	LEVEES	321.598
16	13	PUMPING PLANTS	311.175
17	15	FLOODWAY CONTRO	312.444
18	16A	BANK STABILIZAT	296.614
19	16B	BANK STABILIZAT	302.107

PAUSE TO CONTINUE TYPE- GO, TO STOP TYPE- STOP  
I>go

Figure 4. (Cont'd).

# LINEAR PROJECTIONS FOR QUARTER 4 OF YEAR 1984

1	03	RESERVOIR	408.631
2	04A	EARTH DAM	389.882
3	04B	CONCRETE DAM	377.379
4	05	LOCK	382.995
5	07	POWER PLANTS	383.936
6	08A	ROADS	394.100
7	08B1	CONCRETE BRIDGE	377.782
8	08B2	STEEL BRIDGE	388.331
9	08C	RAIL ROAD	377.469
10	09A	CHANNELS & CANA	398.111
11	09B	CHANNELS & CANA	408.150
12	10	BREAK WATERS	410.467
13	11A	LEVEES	386.234
14	11B	LEVEES	413.664
15	11C	LEVEES	396.909
16	13	PUMPING PLANTS	378.329
17	15	FLOODWAY CONTRO	378.783
18	16A	BANK STABILIZAT	379.041
19	16B	BANK STABILIZAT	380.457

PAUSE TO CONTINUE TYPE- GO, TO STOP TYPE- STOP  
I>go  
\*  
C>

Figure 4 (Cont'd).



## APPENDIX:

### CWCCIS AND THE PRINCIPLES OF COST INDEXING

CWCCIS provides national cost indices specific to 19 major construction types, or "features" (Table A1). The feature indices are computed from three levels of subindices, which provide increasing detail (Figure A1). The first level below the feature consists of indices for five primary categories of work — earthwork, concrete, steel, mechanical, and electrical — and a secondary category, buildings. The third level breaks each category into labor, plant, and material resource classes. The most specific level provides indices for the actual types of resources used in the construction for each resource class.

For CWCCIS, indices were not developed for each resource type; rather, key indicators containing resources whose index values change at the same rate were chosen to provide a manageable number of indicators, yet still account for most of the cost for a particular feature. Any remaining resource types, each of which contributed less than 1 percent of the costs, were placed in the "Other" category (Figure A1). To develop the system, more than 80 detailed Government estimates were analyzed. The resources were weighted according to their importance to a specific project. Thus, a resource that is not needed to build a dam, for example, is not considered in an index provided to the user who is figuring costs for a dam. This feature of the system makes the cost figures far more accurate.

This appendix outlines the principles of indexing and explains the importance of weighting schemes in calculating index numbers.

#### Index Numbers

An index number is a ratio between the cost of a resource or composite of resource costs at one period of time and the cost of the same resource or composite at a specific previous date or period called the base period (or base year). The index number thus indicates the percent change in cost that has resulted from inflation between the base period and the later date.

For example, assume that in 1967 1 cwt of cement cost \$1.20 and that in 1976 the cost was \$2.53. If 1967 is taken as the base year, then the index value for a cwt of cement in 1976 is:

$$\frac{2.53}{1.20} = 2.108$$

or as it is usually expressed, 210.8. This index value indicates that from 1967 to 1976 the cost of a unit of cement rose 2.108 times.

There are two types of index numbers: simple, consisting of a single commodity, and composite, comprising several different commodities. The example above is a simple index.

**Table A1**

**Features for Which Indices Were Developed**

1. Reservoirs
2. Dams, earth
3. Dams, concrete
4. Locks
5. Power plants
6. Roads
7. Concrete bridges
8. Steel bridges
9. Railroads
10. Channels and canals  
(Based on estimates containing only earthwork job items)
11. Channels and canals  
(Based on estimates containing both earthwork and concrete work. This feature provides for concrete lining, concrete slope protection and drainage systems in addition to the earthwork found in feature 10.)
12. Breakwaters and seawalls
13. Levees and floodwalls  
(Based on estimates for levees with heaped earth with aggregate or riprap slope protection)
14. Levees and floodwalls  
(Based on combination of levees and floodwalls that have structural concrete work including walls or slope protection)
15. Levees and floodwalls  
(Based on estimates that have levees, floodwalls, and floodgates and contain all five primary categories of work)
16. Pumping plants
17. Floodway control and diversion structures
18. Bank stabilization  
(Based on estimates with only earthwork category)
19. Bank stabilization  
(Based on estimates with large amounts of riprap slope protection and major drainage systems)




Figure A1. Hierarchy of levels in CHOCIS.

Composite indices are more difficult to construct and interpret than simple indices. Nevertheless, only composite indices, with which this report is concerned, yield useful insights into cost inflation.

There are three problems in index number construction:

1. Selection of items to be included. Over 2000 items are purchased for a typical building project. The Bureau of Labor Statistics measures only about 400 of these goods and services, which reflect the average change in the entire construction project.

2. Choice of a base period from which to calculate change in prices. Whatever the date chosen, the level of prices in the base period is taken as 100. The further away one moves in time from the base period, the dimmer one's recollection of the conditions prevailing; consequently, bases are shifted periodically to more current time periods.

3. Selection of weights to be used. Since the individual items included in the index are not equally important, weighting schemes are usually applied to give each item its proper influence in the index number calculation. For example, the cost of nails is usually not as important a share of total costs as labor. Consequently, changes in labor costs should carry greater weight than nails in cost index calculations.

#### Weighting

The problems of weighting can be illustrated by creating a simplified composite construction price index for the period 1980 to 1981. Assume that the index has only four components -- labor, nails, lumber, and paint -- and that in 1980 and 1981 the costs of these four materials were as shown in Table A2.

A crude composite construction cost index could be constructed by simply totaling all the resource costs in each year, taking the ratio of these totals, and multiplying by 100. This is to say,

$$\text{Construction cost index} = \frac{26.50}{20.50} \times 100 = 129.3.$$

This index means that the same commodities and services purchased in 1980 would cost 29.3 percent more if purchased in 1981.

Suppose that another commodity is added to this cost index -- gold faucets. The revised figures are shown in Table A3. Now the construction cost index reads:

$$\frac{426.50}{620.50} \times 100 = 68.7,$$

representing a decline in cost of 31.2 percent. The point is this: the overall index declined even though the price of four of the commodities increased and only one declined. Moreover, the higher priced commodity was one which is very unimportant in the budgets of most construction projects.

**Table A2**  
**Costs of Four Construction Inputs**

	<u>1980 Cost</u>	<u>1981 Cost</u>
Labor (1 hr)	\$7.00	\$8.50
Nails (1 box)	2.50	3.50
Lumber (1 2x4)	5.00	6.50
Paint (1 gal)	<u>6.00</u>	<u>8.00</u>
Total:	\$20.50	\$26.50

**Table A3**  
**Costs of Five Construction Inputs**

	<u>1980 Cost</u>	<u>1981 Cost</u>
Labor (1 hr)	\$7.00	\$8.50
Nails (1 box)	2.50	3.50
Lumber (1 2x4)	5.00	6.50
Paint (1 gal)	6.00	8.00
Gold faucets (1 faucet)	<u>600.00</u>	<u>400.00</u>
Total:	\$620.50	\$426.50

This implies that commodities included in an index must be weighted by their relative importance to the project.

Another deficiency of this type of index is the arbitrary nature of the units on which the prices are based. For example, Table A4 shows the figures if the price of labor were stated in terms of per minute rather than per hour. So the cost index would read:

$$\frac{18.14}{13.62} \times 100 = 133.2,$$

instead of 129.3.

The results shown in Tables A3 and A4 indicate that a reasonable weighting scheme must be adopted. This would take into account the relative importance of each item and would insulate the index from arbitrary differences in units of measure. For a construction cost index, reasonable weights would be given by the usual amounts of the commodity purchased for a typical construction project. These are called "quantity" weights, since they represent quantities of goods or services purchased.

Table A5 is an example of such a weighting scheme. It assumes that 1 hr of labor, three boxes of nails, two 2 x 4 boards, and 1 gal of paint were used for the "typical" construction project built in both 1980 and 1981. The two columns on the right show the 1980 and 1981 prices of these inputs multiplied or "weighted" by these quantities. These two weighted columns provide the bases for the construction cost index.

The construction cost index using weighted prices is thus:

$$\frac{40.00}{30.50} \times 100 = 131.1$$

This figure more accurately reflects construction cost inflation because each of the materials is weighted according to its relative importance in a construction project. Note that if the units in which the commodities are measured change, the weights also change to compensate.

The general formula for this type of index (called a Laspeyres index) is:

$$\frac{\sum P_n \cdot Q_o}{\sum P_o \cdot Q_o} \times 100 \quad [\text{Eq A1}]$$

where:  $P_o$  = price in base period  
 $P_n$  = price in non-base period  
 $Q_o$  = quantity in a base period.

This is the formula used by CERL's Civil Works construction cost index, which attempts to measure how much it would cost (at retail) to purchase the goods and services needed to build a typical Civil Works project, compared with what it would have cost in a base period. The quantity weights used in this index were derived from a careful survey in 1980 of the goods and

services used for representative Corps projects. The items measured are listed in Table A6.

New construction techniques eventually may be developed and commodity prices may change. Cheaper substitutes may be found for expensive materials or altogether new materials may be introduced into the construction process. Thus, the relative importance of individual products and services changes over time, and weights must be periodically updated. Fortunately, engineering principles and techniques do not change as rapidly as prices, so the weights should not have to be re-examined or resurveyed more than once every 5 or 10 years. In fact, a single resurvey in 1990 may be adequate if technological changes in civil works construction are moderate enough, and if limited budgets prevent more frequent surveys. Projects used in a resurvey should be randomly selected so that accurate inferences can be drawn for all Corps construction projects. The price information used by the computerized CWCCIS is subject to much greater variability, and therefore is updated more frequently by the Office of the Chief of Engineers.

Table A4  
Costs of Four Construction Inputs — Price of  
Labor in Minutes

	<u>1980 Cost</u>	<u>1981 Cost</u>
Labor (1 min)	\$0.12	\$0.14
Nails (1 box)	2.50	3.50
Lumber (1 2x4)	5.00	6.50
Paint (1 gal)	<u>6.00</u>	<u>8.00</u>
Total:	\$13.62	\$18.14

Table A5  
Quantity Weighting Scheme

	<u>1980 Cost</u>	<u>1981 Cost</u>	<u>1980 Quantity</u>	<u>1980 Cost x Quantity</u>	<u>1981 Cost x Quantity</u>
Labor (1 hr)	\$7.00	\$8.50	1 hr	\$ 7.00	\$ 8.50
Nails (1 box)	2.50	3.50	3 boxes	7.50	10.50
Lumber (1 2x4)	5.00	6.50	2 pieces	10.00	13.00
Paint (1 gal)	6.00	8.00	1 gal	<u>6.00</u>	<u>8.00</u>
			Total:	\$30.50	\$40.00

Table A6  
Items Surveyed to Derive Quantity Weights

<u>Labor</u>	<u>Plant</u>	<u>Material</u>
Carpenter	Compressor	Cement
Cement mason	Crane	Electrical
Electrician	Mixer, paver	Explosives
Ironworker	Rock drill	Fabricated metal
Laborer	Scraper-grader	Lumber
Operator	Special machine	Miscellaneous metal
Painter	Tractor	Rebar
Plumber	Trucks	Aggregate
Truck driver	Welding equipment	Steel plates
Other labor	Other plant	Machinery
		Turbines
		Mattress
		Other material



# CHE DISTRIBUTION

Chief of Engineers  
ATTN: Tech Monitor  
ATTN: SAMS-ASL-L (2)  
ATTN: SAMS-COF  
ATTN: SAMS-CV  
ATTN: SAMS-CHE  
ATTN: SAMS-CHE-A  
ATTN: SAMS-CHE  
ATTN: SAMS-CHE  
ATTN: SAMS-MP  
ATTN: SAMS-MPC  
ATTN: SAMS-MPC  
ATTN: SAMS-MPC  
ATTN: SAMS-MPC  
ATTN: SAMS-MPC-A  
ATTN: SAMS-MPC  
ATTN: SAMS-MPC  
ATTN: SAMS-MPC  
ATTN: SAMS-MPC  
ATTN: SAMS-MPC  
ATTN: SAMS-MPC

FESA, ATTN: Library 22060

FESA, ATTN: DNT III 79906

## US Army Engineer Districts

ATTN: Library  
Alaska 99501  
Al Batis 09616  
Albuquerque 87103  
Baltimore 21203  
Buffalo 14207  
Charleston 29402  
Chicago 60604  
Detroit 48231  
Fort Worth 76102  
Galveston 77550  
Huntington 25721  
Jacksonville 32232  
Japan 96343  
Kansas City 64106  
Little Rock 72203  
Los Angeles 90053  
Louisville 40201  
Memphis 38103  
Mobile 36628  
Nashville 37202  
New Orleans 70160  
New York 10007  
Norfolk 23510  
Omaha 68102  
Philadelphia 19106  
Pittsburgh 15222  
Portland 97208  
Riyadh 09038  
Rock Island 61201  
Sacramento 95814  
San Francisco 94105  
Savannah 31402  
Seattle 98124  
St. Louis 63101  
St. Paul 55101  
Tulsa 74102  
Vicksburg 39180  
Walla Walla 99362  
Wilmington 28401

## US Army Engineer Divisions

ATTN: Library  
Europe 09737  
Monteville 35807  
Lower Mississippi Valley 39180  
Middle East 09038  
Middle East (Near) 22601  
Missouri River 68101  
New England 02154  
North Atlantic 10007  
North Central 68605  
North Pacific 97208  
Ohio River 45201  
Pacific Ocean 96356  
South Atlantic 30363  
South Pacific 94111  
Southwestern 75202

## US Army Europe

HQ, 7th Army Training Command 09114  
ATTN: ACTT-000 (3)  
Hq, 7th Army CEC/Eng. 09403  
ATTN: ASAM-00 (4)  
V. Corps 09079  
ATTN: ACTT-000 (5)  
VII. Corps 09154  
ATTN: ACTT-000 (5)  
21st Support Command 09325  
ATTN: ASAM (5)  
Berlin 09742  
ATTN: ASAM-00 (2)  
Southern European Task Force 09166  
ATTN: ASAM-00 (3)  
Installation Support Activity 09403  
ATTN: ASAM-00

Sub USA, Korea  
ATTN: SAMS (5) 96301  
ATTN: SAMS-T 96328  
ATTN: SAMS-IB 96324  
ATTN: SAMS-AM 96300

Sub USA, Korea  
ATTN: SAMS-T 96371  
ATTN: SAMS-T 96350  
ATTN: SAMS-T 96312  
RML/US Combined Forces Command 96301  
ATTN: RUSA-000-COF/Eng

USA Japan (USARJ)  
CA, FE Wv, A/EN-PE 96343  
Pac Eng (Nagasaki) 96343  
Pac Eng (Osaka) 96331

Rocky M. Area 20903

Area Engineer, AMSC-Area Office  
Arnold Air Force Station, TN 37309

Western Area Office, CA  
Vandenberg AFB, CA 93437

41st Engineer Command 60623  
ATTN: Facilities Engineer

US Military Academy 10996  
ATTN: Facilities Engineer  
ATTN: Dept of Geography &  
Computer Science  
ATTN: DSC/EN/NAEN-A

Eng. Studies Center 20313  
ATTN: Library

AMSC, ATTN: DSC/EN-00 02172

USA ARSCOM 61299

ATTN: DSC/IB-RI-1  
ATTN: DSC/IB-15

DARCOM - Div., Inst., & Svc.  
ATTN: Facilities Engineer  
ABRACOM 07801  
Aberdeen Proving Ground 21005  
Army Mater. and Mechanics Bn. Ctr.  
Casper Christi Army Depot 78419  
Harry Diamond Laboratories 20783  
Dugway Proving Ground 64022  
Jefferson Proving Ground 47250  
Fort Monmouth 07703  
Letterkenny Army Depot 17201  
Natick R&D Ctr. 01760  
New Cumberland Army Depot 17070  
Pueblo Army Depot 81001  
Red River Army Depot 75501  
Rendova Arsenal 35809  
Rock Island Arsenal 61299  
Savanna Army Depot 61074  
Sharps Army Depot 95331  
Socoma Army Depot 14561  
Tobyhanna Army Depot 18466  
Tooele Army Depot 84074  
Wetervliet Arsenal 12189  
Yuma Proving Ground 85304  
White Sands Missile Range 88002

DLA ATTN: DLA-W1 22314

## FORSCOM Engineer, ATTN: AFEN-PE

ATTN: Facilities Engineer  
Fort Benning 00934  
Fort Bragg 28307  
Fort Campbell 42223  
Fort Carson 80913  
Fort Cavazos 01433  
Fort Drum 13601  
Fort Hood 74344  
Fort Indianhead Gap 17003  
Fort Irwin 92311  
Fort San Houston 78234  
Fort Lewis 98433  
Fort McCoy 34636  
Fort Meade 20755  
Fort Ord 93941  
Fort Polk 71439  
Fort Richardson 95505  
Fort Riley 66443  
Frontera of San Francisco 94129  
Fort Sheridan 60037  
Fort Stewart 31213  
Fort Vainwright 99783  
Vancouver Bn. 98000

WEC  
ATTN: WEC-T 70234  
ATTN: Facilities Engineer  
Pittsburgh AMC 80040  
Walter Reed AMC 20012

INSCOM - Ch, Instl. Div.  
ATTN: Facilities Engineer  
Arlington Hall Station (1) 22213  
Vine Hill Force Station 20120

WEC  
ATTN: Facilities Engineer  
Cameron Station 22314  
Fort Leakey J. H. H. 20015  
Fort Rye 22211

WEC  
ATTN: WEC-T 20015  
ATTN: Facilities Engineer  
Oakland Army Bn. 94506  
Savanna Bn. 09008  
Sunny Point Bn. 20401

BARACOM, ATTN: BARAC-T 07160

BARCOM, Pac. Div. 40090

## THADOC

HQ, THADOC, ATTN: ASAM-PE  
ATTN: Facilities Engineer  
Port Belvoir 22008  
Port Banning 31005  
Port Hilo 70016  
Port Hilo Barrocas 17013  
Port Hilo 72003  
Port Hilo 00040  
Port Hilo 23004  
Port Hilo 30005  
Port Hilo 11233  
Port San Juan Barrocas 46216  
Port Jackson 20007  
Port Hilo 40121  
Port Hilo 40027  
Port Hilo 23001  
Port Hilo 30205  
Port Hilo 23051  
Port Hilo 30362  
Port Hilo 73003  
Port Leonard Wood 63473

THADOC, ATTN: STEAS-T 63120

## BRAC

ATTN: Facilities Engineer  
Port Hilo 85013  
Port Hilo 21719

WESTCOM  
ATTN: Facilities Engineer  
Port Hilo 96030

## SHADE 09025

ATTN: Survivability Section, CCB-OPS  
Infrastructure Branch, LAMBA

HQ USHCOM 09128

ATTN: BCI 477-LOH

Port Belvoir, VA 22060

ATTN: ATTA-000-00  
ATTN: ATTA-000-00  
ATTN: ATTA-00  
ATTN: Eng. Library  
ATTN: Canadian Liaison Office (2)  
ATTN: ENR Library

Cold Regions Research Engineering Lab 03753  
ATTN: Library

ETL, ATTN: Library 22060

Waterways Experiment Station 39180  
ATTN: Library

HQ, XVIII Airborne Corps and 28307  
Ft. Bragg  
ATTN: AFPA-PE-02

Chamota AFB, IL 61866  
3045 CEN/EN, Stop 27

Horton AFB 20409

ATTN: AFPC-000/ENR

Tyndall AFB, FL 32403  
AFPC/Engineering & Service Lab

## NAFPC

ATTN: USARL Liaison Office  
Atlantic Division 23011  
Chesapeake Division 20374  
Southern Division 20411  
Pacific Division 00000  
Northern Division 19112  
Western Division 04004  
ATTN: Sr. Tech. P&D-00T 22330  
ATTN: Asst. CEN R&D, P&D-03 22332

WEC 22041

ATTN: Library (Code LOMA)

Defense Technical Info. Center 22314  
ATTN: DSI (12)

Engineering Section Library 10017  
New York, NY

National Guard Bureau 20310  
Installation Division

US Government Printing Office 20304  
Receiving Section/Repository Copies (2)

Bagby, D. Gordon

Computerized Civil Works Construction Cost Index System : user's manual / by D. Gordon Bagby, Shahid Siddiqi. — Champaign, Ill : Construction Engineering Research Laboratory ; available from NTIS, 1982.

29 p. (Technical report / Construction Engineering Research Laboratory ; P-135)

1. Public works - costs. 2. Building - estimates. 3. Civil Works. Construction Cost Index System. I. Siddiqi, Shahid. II. Title. III. Series: Technical report (Construction Engineering Research Laboratory) ; P-135.